

ADDENDUM NO. 2

TO: ALL PLAN HOLDERS

ISSUED BY: _____

Hugo Elizondo, Jr.
Hugo Elizondo, Jr., P.E.
Cuatro Consultants, Ltd.
3601 Kyle Crossing, Suite A
Kyle, TX 78640

DATE _____

4/5/21

**RE: 281 SOUTH COMMERCIAL PARK
SUBDIVISION IMPROVEMENTS**



Please note the following clarifications/revisions of the bid documents as per earlier discussions.

1. Bidders shall note the revised Bid Items below and updated Bid Proposal Sheets attached hereto.

Deleted Bid Item.

23 1 LS

Furnish all labor, material and equipment to construct
STANDARD HEADWALL FOR 2 - 5' X 5' BOX
CULVERTS at Channel "A", Station 1+34.00, per TxDOT
Detail, upstream, complete per lump sum for,
\$ _____.

Revised description of Bid Item.

57 3 EA

Proposed 12 to Existing 12

Revised Quantity of Bid Item.

65 3 EA

Furnish all labor, material, and equipment to construct
MANHOLE ON EXISTING LINE, complete, per each
for, \$ _____.

SUPPLEMENTAL BID "B": Houston Clinton Drive Street Improvements

Revised Quantity of Bid Item.

1 341 LF

Furnish and install SILT FENCE, complete, per linear foot
for, \$ _____.

Revised description of Bid Item.

6 1.81 AC Furnish all labor, material, and equipment to CLEAR AND GRUB AND ROUGH CUT STREET INCLUDING DEMOLITION OF THE EXISTING STREET, complete, per acre for, \$_____.

Add Bid Item.

19A 55 LF Furnish all and install 3 EA – 5' x 2' MULTIPLE BOX CULVERTS (ALL DEPTHS), per TxDOT Details, complete, per linear foot for, \$_____.

Add Bid Item.

20A 1 LS Furnish and install PARALLEL HEADWALL WITH CONCRETE RIPRAP FOR OR 3 EA – 5' X 2' BOX CULVERTS at Station 0+22.53, per TxDOT Detail, upstream, complete per lump sum for, \$_____.

Add Bid Item.

21A 1 LS Furnish and install PARALLEL HEADWALL WITH CONCRETE RIPRAP FOR OR 3 EA – 5' X 2' BOX CULVERTS at Station 0+77.42, per TxDOT Detail, upstream, complete per lump sum for, \$_____.

Add Bid Item.

22A 1 LS Furnish and install CONNECTIONS TO EXISTING DRIVEWAYS WITH SAW CUT, complete per lump sum for, \$_____.

Add Bid Item.

23A 1 LS Furnish all labor, material, and equipment to CONSTRUCT, STAKE AND POUR CONCRETE TRICKLE CHANNEL, per standard detail, complete, per lump sum for, \$_____.

Add Bid Item.

24A 1 LS Furnish all labor, material, and equipment to CONSTRUCT, STAKE AND POUR SPECIAL CURB INLET AND CONCRETE FLUME, per standard detail, complete, per lump sum for, \$_____.

Bidder shall acknowledge receipt of Addendum No. 1 on their Bid Proposal.

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS**

Proposal of _____ (hereinafter called "Bidder"),
doing business as a corporation/a partnership/an individual (strike out inapplicable terms), to the City
of Burnet Economic Development Corporation (hereinafter called "Locality").

Gentlemen:

The Bidder, in compliance with your invitation for bids for the construction of 281 South Commercial Park
Subdivision Improvements, having examined the Plans and Specifications and related
Documents, the Site of the proposed work, and being familiar with all of the conditions surrounding the
construction of the proposed Project including the availability of materials and labor, hereby proposes
to furnish all labor, materials, and supplies, and to construct the Project in accordance with the Plans,
Specifications and Contract Documents, within the time setforth therein, and at the unit prices stated
below. These unit prices are to cover all expenses incurred in performing the work required under the
Contract Documents, of which this Proposal is part.

Bidder herby agrees to commence work under this Contract on or before a date to be written "Notice
to Proceed" by the Owner and to fully complete the project within _____ consecutive
calendar days thereafter. Bidder further agrees to pay as liquidated damages the sum setforth in the
Special Conditions for each consecutive calendar day thereafter.

Bidder acknowledges receipt of the following ADDENDA:

Addendum No.1 dated _____ Received _____

Addendum No. 2 dated _____ Received _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

BID SCHEDULE:

PROPOSAL "A": EROSION / SEDIMENTATION CONTROL

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
1	1	LS	Furnish and install STABILIZED CONSTRUCTION ENTRANCE, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
2	1,331	LF	Furnish and install SILT FENCE, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
3	70	LF	Furnish and install ROCK BERM, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
4	2	EA	Furnish and install INLET PROTECTION, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
5	1	LS	Furnish and install CONCRETE WASHOUT STATION, per detail shown on Plans, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
6	4,500	SY	Furnish and install REVEGETATION OF STREET R.O.W. (hydroseed including watering), complete, per square yard for, _____ Dollars and _____ Cents	\$ _____	\$ _____
7A	1	LS	Furnish all labor and equipment to complete DEMOLITION, as shown on Sheet 9 of 35, including removing material offsite, per lump sum for, _____ Dollars and _____ Cents	\$ -	\$ -

TOTAL AMOUNT OF PROPOSAL "A"
(Sum of Items 1 through 7A)

_____ Dollars				
and _____ Cents			\$ _____	

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

PROPOSAL "B": STREET AND DRAINAGE IMPROVEMENTS

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
7	1	LS	Furnish all labor and equipment to complete MOBILIZATION for the project start, for the lump sum of, _____ Dollars and _____ Cents	\$ _____	\$ _____
8	1	LS	Furnish PERFORMANCE AND PAYMENT BONDS. 100 percent, per requirements in specifications for the lump sum of, _____ Dollars and _____ Cents	\$ _____	\$ _____
9	1.33	AC	Furnish all labor, material, and equipment to CLEAR AND GRUB AND ROUGH CUT STREET, complete, per acre for, _____ Dollars and _____ Cents	\$ _____	\$ _____
10	4,690	SY	Furnish all labor, material, and equipment for SUBGRADE PREPARATION (3' BEHIND CURB) including 8" of moisture conditioned subgrade, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
11	4,690	SY	Furnish all labor, material, and equipment to install 12" CRUSHED STONE FLEXIBLE BASE (3' BEHIND CURB), per TxDOT Item 247, complete, per square yard for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
12	3,668	SY	Furnish all labor, material, and equipment to install 2" HMAC, Type D, TxDOT Item 340, complete, per square yard for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
13	1,812	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE CURB AND GUTTER, complete, per linear foot for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
14	97	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE RIBBON CURB, complete, per linear foot for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
15	1	LS	Furnish all labor, material, and equipment to construct COMMERCIAL DRIVEWAY APRON, TYPE II, for Lot 1, per detail shown on Plans, complete, per lump sum for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
16	2	EA	Furnish all labor, material, and equipment to install STREET SIGNS, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
17	2	EA	Furnish and install STANDARD 10' CURB INLETS, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
18	209	LF	Furnish and install 2 EA - 5' x 5' MULTIPLE BOX CULVERTS (ALL DEPTHS) per TxDOT Details, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
19	45	LF	Furnish and install 30" RCP, CLASS III (ALL DEPTHS), complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
20	278	LF	Furnish and install 24" RCP, CLASS III (ALL DEPTHS), complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
21	13	LF	Furnish and install 18" RCP, CLASS III (ALL DEPTHS), complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
21A	116	LF	Furnish and install 2 EA 18" RCP, CLASS III (ALL DEPTHS), complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
22	1	LS	Furnish all labor, material and equipment to construct STANDARD HEADWALL FOR 2 - 5' X 5' BOX CULVERTS at Channel "A", Station 1+34.00, per TxDOT Detail, upstream, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
23			DUPLICATE ITEM HAS BEEN DELETED _____ Dollars and _____ Cents	\$ _____	\$ _____
24	1	LS	Furnish and install PARALLEL HEADWALL FOR 2 EA - 5' x 5' BOX CULVERTS at Channel "A", Station 6+26.72, per TxDOT detail, downstream, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
25	1	EA	Furnish and install SLOPED HEADWALL FOR 30" RCP, including scour protection, complete, per each for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
26	2	EA	Furnish and install SLOPED HEADWALL FOR 24" RCP, including scour protection, complete, per each for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
27	1	EA	Furnish and install SLOPED HEADWALL FOR 2 - 18" RCP, including scour protection, complete, per each for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
28	1	LS	Furnish all labor, material, and equipment to construct CONCRETE CHANNEL STRUCTURE "A" AT DOWNSTREAM END OF 5' x 5' BOX CULVERTS in Channel "A", Station 5+97.43, per detail shown on Plans, complete, per lump sum for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
29	1	LS	Furnish all labor, material, and equipment to construct CONCRETE DROP STRUCTURE "B" AT UPSTREAM END OF 5' x 5' BOX CULVERTS in Channel "A", Station 7+20.00, per detail shown on Plans, complete, per lump sum for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
30	1	LS	Furnish all labor, material, and equipment to construct CONCRETE DROP STRUCTURE "C" AT UPSTREAM END of Channel "A", Station 9+95.00, per detail shown on Plans, complete, per lump sum _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
31	452	LF	Furnish all labor, material, and equipment to construct CHANNEL "A", 18' WIDE BOTTOM, concrete riprap at 1:1 side slopes, excavation, embankment, and revegetation, complete, per linear foot for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
32	278	LF	Furnish all labor, material, and equipment to construct CHANNEL "A", 15' WIDE EARTHEN BOTTOM, at 3:1 side slopes, excavation, embankment, and revegetation, complete, per linear foot for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
33	449	LF	Furnish all labor, material, and equipment to construct CHANNEL "B", 3' WIDE EARTHEN BOTTOM, at 3:1 side slopes, excavation, embankment, and revegetation, complete, per linear foot for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
34	1	LS	Furnish all labor, material, and equipment to REMOVE EXISTING HEADWALL AT 5' X 5' BOX CULVERTS AND CONNECT NEW 5' X 5' BOX CULVERTS, complete, for the lump sum of, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
35	1	LS	Furnish all labor, material, and equipment to provide PAVEMENT STRIPING, including stop bars, complete, per lump sum for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
36	7	LOT	Furnish all labor, material, and equipment to provide GRADING FOR DRAINAGE PURPOSES, including all excavation and embankment, complete, per lot for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
37	91	LF	Furnish all labor, material, and equipment to SAW CUT EXISTING ASPHALT AT HOUSTON CLINTON DRIVE, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
38	1,890	LF	Furnish all labor, material, and equipment to construct 5' CONCRETE SIDEWALK, including excavation and backfield, per detail shown on Plans, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
39	776	LF	Furnish and install TRENCH SAFETY SYSTEM, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

TOTAL AMOUNT OF PROPOSAL "B" (Sum of Items 7 through 39)					
				_____ Dollars	
				and _____ Cents	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

PROPOSAL "C": TXDOT DECELERATION LANE

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
40	49	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE CURB AND GUTTER, per detail shown on Plans, complete, per linear foot for, _____ Dollars _____ Cents	\$ _____	\$ _____
41	197	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE RIBBON CURB, per detail shown on Plans, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
42	400	SY	Furnish all labor, material, and equipment to lay 2" HMAC, Type D, TxDOT Item 340, complete, per square yard for, _____ Dollars and _____ Cents	\$ _____	\$ _____
43	507	SY	Furnish all labor, material, and equipment for SUBGRADE PREPARATION, complete, per square yard for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
44	507	SY	Furnish all labor, material, and equipment to place 12" CRUSHED STONE FLEXIBLE BASE (3' BEHIND CURB), per TxDOT Item 247, complete, per square yard for, _____ _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
45	275	LF	Furnish all labor, material, and equipment to SAW CUT CURB AT EXISTING PAVEMENT, complete, per linear foot for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
46	175	LF	Furnish all labor, material, and equipment to REMOVE GUARDRAIL, complete, per linear foot for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
47	1	LS	Furnish all labor, material, and equipment for TRAFFIC CONTROL, per TxDOT requirements, complete, per lump sum for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
48	1	LS	Furnish and install, TxDOT PAVEMENT MARKINGS AND SIGNS, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
49	385	LF	Furnish all labor, material, and equipment to construct 5' CONCRETE SIDEWALK along US Highway 281, including excavation, wall footing, compactED fill and handrail, per detail shown on Plans, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

TOTAL AMOUNT OF PROPOSAL "C" (Sum of Items 40 through 49)					
_____ Dollars and _____ Cents					
				\$ _____	\$ _____

PROPOSAL "D": WATER IMPROVEMENTS

50	2,133	LF	Furnish and install 12" PVC MAIN, DR 14, ALL DEPTHS, including fittings, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
----	-------	----	-------------------------------------------------------------------------------------------------------------------------------------------------	----------	----------

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
51	5	EA	Furnish and install NEW FIRE HYDRANT, ASSEMBLY - 6" VALVE AND DI LEAD PIPE, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
52	6	EA	Furnish and install TWO-INCH METER SETTING, long and short side, per detail shown on Plans, complete, per each for _____ Dollars and _____ Cents	\$ _____	\$ _____
53	1	EA	Furnish and install NEW 2" METER AT EXISTING CARWASH, transfer from existing main to be abandoned, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
54	1	EA	Furnish and install NEW 2" METER SETTING on existing 8" main, to serve Lot 1, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
55	13	EA	Furnish all labor, material, and equipment to RAISE VALVE CASTINGS, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
56	8	EA	Furnish and install 12" GATE VALVE WITH BOX, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
57	3	EA	Furnish all labor, material, and equipment to complete WET CONNECTIONS TO EXISTING MAINS, complete, per each for, Proposed 12 to Existing 12 _____ Dollars and _____ Cents	\$ _____	\$ _____
	1	EA	Proposed 8 to Existing 8 _____ Dollars and _____ Cents	\$ _____	\$ _____
58	1	LS	Furnish all labor, material, and equipment to CUT AND PLUG EXISTING 8" BRANCH on existing 12" x 8" Tee, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
59	2,133	LF	Furnish and install TRENCH SAFETY SYSTEM, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

TOTAL AMOUNT OF PROPOSAL "D"
(Sum of Items 50 through 59)

_____ Dollars		
and _____ Cents	\$	\$ _____

PROPOSAL "E": WASTEWATER IMPROVEMENTS

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
60	13	LF	Furnish and install 12" WASTEWATER LINE PVC, SDR 26 (0-8' DEEP), at the grades shown on the Plans, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

61	84	LF	Furnish and install 12" WASTEWATER LINE PVC, SDR 26 (8-10' DEEP), at the grades shown on the Plans, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
----	----	----	------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------	----------

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
62	33	LF	Furnish and install 8" WASTEWATER LINE PVC, SDR 26 (0'-8' DEEP), at the grades shown on the Plans, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
63	367	LF	Furnish and install 8" WASTEWATER LINE PVC, SDR 26 (8'-10' DEEP), at the grades shown on the Plans, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
64	4	EA	Furnish and install WASTEWATER MANHOLE, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
65	3	EA	Furnish all labor, material, and equipment to construct MANHOLE ON EXISTING LINE, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
66	7	VF	Furnish and install MANHOLE EXTRA DEPTH, complete, per vertical foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
67	6	VF	Furnish all labor, material, and equipment to RAISE EXISTING MANHOLE TO FINISHED GRADE, complete, per vertical foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
68	5	EA	Furnish and install SINGLE WASTEWATER SERVICE, from service wye to two-way cleanout at property line, as per detail shown on Plans, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
69	1	EA	Furnish and install DOUBLE WASTEWATER SERVICE, from manhole to new service manhole at property line, as per detail shown on Plans, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
70	1	LS	Furnish all labor, material, and equipment to CONNECT TO EXISTING MAIN, complete, per _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
71	497	LF	Furnish and install TRENCH SAFETY SYSTEM, complete, per linear foot for,		
			_____ Dollars		
			and _____ Cents	\$ _____	\$ _____

TOTAL AMOUNT OF PROPOSAL "E"
 (Sum of Items 60 through 71)

_____ Dollars		
and _____ Cents	\$ _____	

TOTAL AMOUNT OF BASE BID "A"
 (Sum of Items 1 through 71)

_____ Dollars		
and _____ Cents	\$ _____	

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
 SUPPLEMENTAL BID "B"

BID SCHEDULE:

PROPOSAL "A": EROSION / SEDIMENTATION CONTROL

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
1	341	LF	Furnish and install SILT FENCE, complete, per linear foot for, _____ _____ Dollars and _____ Cents		\$ -
2	1	LS	Furnish and install CONCRETE WASHOUT STATION, per detail shown on Plans, complete, per lump sum for, _____ _____ Dollars and _____ Cents		\$ -
3	3,107	SY	Furnish and install REVEGETATION OF STREET R.O.W. (hydroseed including watering), complete, per square yard for, _____ _____ Dollars and _____ Cents	_____	\$ -

TOTAL AMOUNT OF PROPOSAL "A"					
(Sum of Items 1 through 3)					
				_____ Dollars	
				and _____ Cents	\$ -

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
 SUPPLEMENTAL BID "B"

PROPOSAL "B": STREET AND DRAINAGE IMPROVEMENTS

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
4	1	LS	Furnish all labor and equipment to complete MOBILIZATION for the project start, for the lump sum of, _____ _____ Dollars and _____ Cents	_____	\$ _____ -
5	1	LS	Furnish PERFORMANCE AND PAYMENT BONDS. 100 percent, per requirements in specifications for the lump sum of, _____ _____ Dollars and _____ Cents	_____	\$ _____ -
6	1.81	AC	Furnish all labor, material, and equipment to CLEAR AND GRUB AND ROUGH CUT STREET INCLUDING DEMOLITION OF THE EXISTING STREET, complete, per acre for, _____ _____ Dollars and _____ Cents	_____	\$ _____ -
7	6,267	SY	Furnish all labor, material, and equipment for SUBGRADE PREPARATION (3' BEHIND CURB) including 8" of moisture conditioned subgrade, _____ _____ Dollars and _____ Cents	_____	\$ _____ -

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
SUPPLEMENTAL BID "B"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
8	6,267	SY	Furnish all labor, material, and equipment to install 11" CRUSHED STONE BASE (3' BEHIND CURB), per TxDOT Item 247, complete, per square yard for, _____ Dollars and _____ Cents	_____	\$ -
9	6,267	SY	Furnish all labor, material, and equipment to install GEOGRID, TENSAR TX5, per square yard for, _____ Dollars and _____ Cents	_____	\$ -
10	5,158	SY	Furnish all labor, material, and equipment to install 2" HMAC, Type D over 2" HMAC Type C, TxDOT Item 340, complete, per square yard for, _____ Dollars and _____ Cents	_____	\$ -
11	2,640	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE RIBBON CURB, complete, per linear foot for, _____ Dollars and _____ Cents	_____	\$ -
12	2,508	LF	Furnish all labor, material, and equipment to construct 5' CONCRETE SIDEWALK, including excavation and backfield, per detail shown on Plans, complete, per linear foot for, _____ Dollars and _____ Cents	_____	\$ -

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
 SUPPLEMENTAL BID "B"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
13	3	EA	Furnish all labor, material, and equipment to install STREET SIGNS, complete, per each for, _____ Dollars and _____ Cents	_____	\$ -
14	1	LS	Furnish all labor, material, and equipment to provide PAVEMENT STRIPING, including stop bars. _____ Dollars and _____ Cents	_____	\$ -
15	1	LS	Furnish all labor, material, and equipment to provide GRADING FOR DRAINAGE PURPOSES, including all excavation and embankment, complete, per lot for, _____ Dollars and _____ Cents	_____	\$ -
16	60	LF	Furnish all labor, material, and equipment to SAW CUT EXISTING ASPHALT AT HOUSTON CLINTON DRIVE, per linear foot for, _____ Dollars and _____ Cents	_____	\$ -
17	4	LS	Furnish all labor, material, and equipment to REMOVE AND RELOCATE EXISTING ELECTRICAL TRANSFORMERS. _____ Dollars and _____ Cents	_____	\$ -

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
SUPPLEMENTAL BID "B"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
18	1	LS	Furnish all labor, material, and equipment to REMOVE AND RELOCATE EXISTING GUARD RAILS. _____ Dollars and _____ Cents	_____	\$ _____
19A	55	LF	Furnish all and install 3 EA – 5' x 2' MULTIPLE BOX CULVERTS (ALL DEPTHS), per TxDOT Details, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
20A	1	LS	Furnish and install PARALLEL HEADWALL WITH CONCRETE RIPRAP FOR OR 3 EA – 5' X 2' BOX CULVERTS at Station 0+22.53, per TxDOT Detail, upstream, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
21A	1	LS	Furnish and install PARALLEL HEADWALL WITH CONCRETE RIPRAP FOR OR 3 EA – 5' X 2' BOX CULVERTS at Station 0+77.42, per TxDOT Detail, upstream, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
22A	1	EA	Furnish and install CONNECTIONS TO EXISTING DRIVEWAYS WITH SAW CUT, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
23A	1	LS	Furnish all labor, material, and equipment to CONSTRUCT, STAKE AND POUR CONCRETE TRICKLE CHANNEL, per standard detail, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
 SUPPLEMENTAL BID "B"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
24A	1	LS	Furnish all labor, material, and equipment to CONSTRUCT, STAKE AND POUR SPECIAL CURB INLET AND CONCRETE FLUME, per standard detail, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

TOTAL AMOUNT OF PROPOSAL "B"
 (Sum of Items 4 through 24)

_____ Dollars		
and _____ Cents	\$	-

TOTAL AMOUNT OF SUPPLEMENTAL BID "B"
 (Sum of Items 1 through 24)

_____ Dollars		
and _____ Cents	\$	-

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
S. WATER STREET (U.S. HWY 281)**

It is understood that the description of work to be done at prices is intended principally to serve as a guide in evaluating bids and is not intended to fully describe all work required. It is further agreed that the work to be done and material to be furnished at unit prices may be increased or diminished as may be considered necessary in the opinion of the Engineer and approved by the Owner to complete the work fully as planned and contemplated, and that estimated quantities may be increased to cover additional work ordered by the Engineer and approved by the Owner, but not shown on the plans or required by the Specifications, in accordance with the provision of the General Conditions. Similarly, they may be decreased to cover deletion of the work so ordered.

The foregoing prices shall include all labor, materials, removal, overhead, profit, insurance, etc., to cover the finished work called for. Changes shall be proposed in accordance with applicable provisions of the General Conditions.

Bidder understands that the Owner reserves the right to reject any or all bids and to waive any informalities in the bidding.

The bidder agrees that his bid shall be good and may not be withdrawn for a period of ten (10) calendar days after the scheduled closing time for receiving bids.

Upon receipt of written notice of the acceptance of this bid, Bidder will execute the formal contract attached within ten (10) days and deliver Surety Bonds as required by the Special Conditions.

The bid security attached in the sum of five percent (5%) of the bid amount is to become the property of the Owner in the event the contract and bond are not excuted within the time above setforth, as liquidated damages for the delay and additional expense to the Owner caused thereby.

Respectfully submitted: _____

Bidder: _____

Title: _____

(SEAL- if bid by
a corporation)

Address: _____

Phone No.: _____

Date: _____

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS**

Proposal of _____ (hereinafter called "Bidder"),
doing business as a corporation/a partnership/an individual (strike out inapplicable terms), to the City
of Burnet Economic Development Corporation (hereinafter called "Locality").

Gentlemen:

The Bidder, in compliance with your invitation for bids for the construction of 281 South Commercial Park
Subdivision Improvements, having examined the Plans and Specifications and related
Documents, the Site of the proposed work, and being familiar with all of the conditions surrounding the
construction of the proposed Project including the availability of materials and labor, hereby proposes
to furnish all labor, materials, and supplies, and to construct the Project in accordance with the Plans,
Specifications and Contract Documents, within the time setforth therein, and at the unit prices stated
below. These unit prices are to cover all expenses incurred in performing the work required under the
Contract Documents, of which this Proposal is part.

Bidder herby agrees to commence work under this Contract on or before a date to be written "Notice
to Proceed" by the Owner and to fully complete the project within _____ consecutive
calendar days thereafter. Bidder further agrees to pay as liquidated damages the sum setforth in the
Special Conditions for each consecutive calendar day thereafter.

Bidder acknowledges receipt of the following ADDENDA:

Addendum No.1 dated _____ Received _____

Addendum No. 2 dated _____ Received _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

BID SCHEDULE:

PROPOSAL "A": EROSION / SEDIMENTATION CONTROL

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
1	1	LS	Furnish and install STABILIZED CONSTRUCTION ENTRANCE, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
2	1,331	LF	Furnish and install SILT FENCE, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
3	70	LF	Furnish and install ROCK BERM, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
4	2	EA	Furnish and install INLET PROTECTION, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
5	1	LS	Furnish and install CONCRETE WASHOUT STATION, per detail shown on Plans, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
6	4,500	SY	Furnish and install REVEGETATION OF STREET R.O.W. (hydroseed including watering), complete, per square yard for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
7A	1	LS	Furnish all labor and equipment to complete DEMOLITION, as shown on Sheet 9 of 35, including removing material offsite, per lump sum for, _____ _____ Dollars and _____ Cents	\$ -	\$ -

TOTAL AMOUNT OF PROPOSAL "A"
(Sum of Items 1 through 7A)

_____ Dollars

and _____ Cents \$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

PROPOSAL "B": STREET AND DRAINAGE IMPROVEMENTS

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
7	1	LS	Furnish all labor and equipment to complete MOBILIZATION for the project start, for the lump sum of, _____ Dollars and _____ Cents	\$ _____	\$ _____
8	1	LS	Furnish PERFORMANCE AND PAYMENT BONDS. 100 percent, per requirements in specifications for the lump sum of, _____ Dollars and _____ Cents	\$ _____	\$ _____
9	1.33	AC	Furnish all labor, material, and equipment to CLEAR AND GRUB AND ROUGH CUT STREET, complete, per acre for, _____ Dollars and _____ Cents	\$ _____	\$ _____
10	4,690	SY	Furnish all labor, material, and equipment for SUBGRADE PREPARATION (3' BEHIND CURB) including 8" of moisture conditioned subgrade, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
11	4,690	SY	Furnish all labor, material, and equipment to install 12" CRUSHED STONE FLEXIBLE BASE (3' BEHIND CURB), per TxDOT Item 247, complete, per square yard for, _____ Dollars and _____ Cents	\$ _____	\$ _____
12	3,668	SY	Furnish all labor, material, and equipment to install 2" HMAC, Type D, TxDOT Item 340, complete, per square yard for, _____ Dollars and _____ Cents	\$ _____	\$ _____
13	1,812	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE CURB AND GUTTER, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
14	97	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE RIBBON CURB, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
15	1	LS	Furnish all labor, material, and equipment to construct COMMERCIAL DRIVEWAY APRON, TYPE II, for Lot 1, per detail shown on Plans, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
16	2	EA	Furnish all labor, material, and equipment to install STREET SIGNS, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
17	2	EA	Furnish and install STANDARD 10' CURB INLETS, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
18	209	LF	Furnish and install 2 EA - 5' x 5' MULTIPLE BOX CULVERTS (ALL DEPTHS) per TxDOT Details, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
19	45	LF	Furnish and install 30" RCP, CLASS III (ALL DEPTHS), complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
20	278	LF	Furnish and install 24" RCP, CLASS III (ALL DEPTHS), complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
21	13	LF	Furnish and install 18" RCP, CLASS III (ALL DEPTHS), complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
21A	116	LF	Furnish and install 2 EA 18" RCP, CLASS III (ALL DEPTHS), complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
22	1	LS	Furnish all labor, material and equipment to construct STANDARD HEADWALL FOR 2 - 5' X 5' BOX CULVERTS at Channel "A", Station 1+34.00, per TxDOT Detail, upstream, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
23			DUPLICATE ITEM HAS BEEN DELETED _____ Dollars and _____ Cents	\$ _____	\$ _____
24	1	LS	Furnish and install PARALLEL HEADWALL FOR 2 EA - 5' x 5' BOX CULVERTS at Channel "A", Station 6+26.72, per TxDOT detail, downstream, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
25	1	EA	Furnish and install SLOPED HEADWALL FOR 30" RCP, including scour protection, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
26	2	EA	Furnish and install SLOPED HEADWALL FOR 24" RCP, including scour protection, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
27	1	EA	Furnish and install SLOPED HEADWALL FOR 2 - 18" RCP, including scour protection, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
28	1	LS	Furnish all labor, material, and equipment to construct CONCRETE CHANNEL STRUCTURE "A" AT DOWNSTREAM END OF 5' x 5' BOX CULVERTS in Channel "A", Station 5+97.43, per detail shown on Plans, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
29	1	LS	Furnish all labor, material, and equipment to construct CONCRETE DROP STRUCTURE "B" AT UPSTREAM END OF 5' x 5' BOX CULVERTS in Channel "A", Station 7+20.00, per detail shown on Plans, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
30	1	LS	Furnish all labor, material, and equipment to construct CONCRETE DROP STRUCTURE "C" AT UPSTREAM END of Channel "A", Station 9+95.00, per detail shown on Plans, complete, per lump sum _____ Dollars and _____ Cents	\$ _____	\$ _____
31	452	LF	Furnish all labor, material, and equipment to construct CHANNEL "A", 18' WIDE BOTTOM, concrete riprap at 1:1 side slopes, excavation, embankment, and revegetation, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
32	278	LF	Furnish all labor, material, and equipment to construct CHANNEL "A", 15' WIDE EARTHEN BOTTOM, at 3:1 side slopes, excavation, embankment, and revegetation, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
33	449	LF	Furnish all labor, material, and equipment to construct CHANNEL "B", 3' WIDE EARTHEN BOTTOM, at 3:1 side slopes, excavation, embankment, and revegetation, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
34	1	LS	Furnish all labor, material, and equipment to REMOVE EXISTING HEADWALL AT 5' X 5' BOX CULVERTS AND CONNECT NEW 5' X 5' BOX CULVERTS, complete, for the lump sum of, _____ Dollars and _____ Cents	\$ _____	\$ _____
35	1	LS	Furnish all labor, material, and equipment to provide PAVEMENT STRIPING, including stop bars, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
36	7	LOT	Furnish all labor, material, and equipment to provide GRADING FOR DRAINAGE PURPOSES, including all excavation and embankment, complete, per lot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
37	91	LF	Furnish all labor, material, and equipment to SAW CUT EXISTING ASPHALT AT HOUSTON CLINTON DRIVE, per linear foot for, _____ Dollars and _____ Cents	\$	\$
38	1,890	LF	Furnish all labor, material, and equipment to construct 5' CONCRETE SIDEWALK, including excavation and backfill, per detail shown on Plans, complete, per linear foot for, _____ Dollars and _____ Cents	\$	\$
39	776	LF	Furnish and install TRENCH SAFETY SYSTEM, complete, per linear foot for, _____ Dollars and _____ Cents	\$	\$

TOTAL AMOUNT OF PROPOSAL "B"					
(Sum of Items 7 through 39)					
_____ Dollars					
and _____ Cents					
\$ _____					

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

PROPOSAL "C": TxDOT DECELERATION LANE

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
40	49	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE CURB AND GUTTER, per detail shown on Plans, complete, per linear foot for, _____ Dollars _____ Cents	\$ _____	\$ _____
41	197	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE RIBBON CURB, per detail shown on Plans, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
42	400	SY	Furnish all labor, material, and equipment to lay 2" HMAC, Type D, TxDOT Item 340, complete, per square yard for, _____ Dollars and _____ Cents	\$ _____	\$ _____
43	507	SY	Furnish all labor, material, and equipment for SUBGRADE PREPARATION, complete, per square yard for, _____ Dollars and _____ Cents	\$ _____	\$ _____

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
44	507	SY	Furnish all labor, material, and equipment to place 12" CRUSHED STONE FLEXIBLE BASE (3' BEHIND CURB), per TxDOT Item 247, complete, per square yard for, _____ Dollars and _____ Cents	\$ _____	\$ _____
45	275	LF	Furnish all labor, material, and equipment to SAW CUT CURB AT EXISTING PAVEMENT, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
46	175	LF	Furnish all labor, material, and equipment to REMOVE GUARDRAIL, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
47	1	LS	Furnish all labor, material, and equipment for TRAFFIC CONTROL, per TxDOT requirements, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
48	1	LS	Furnish and install, TxDOT PAVEMENT MARKINGS AND SIGNS, complete, per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
49	385	LF	Furnish all labor, material, and equipment to construct 5' CONCRETE SIDEWALK along US Highway 281, including excavation, wall footing, compactED fill and handrail, per detail shown on Plans, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

TOTAL AMOUNT OF PROPOSAL "C" (Sum of Items 40 through 49)					
_____ Dollars and _____ Cents					
				\$ _____	\$ _____

PROPOSAL "D": WATER IMPROVEMENTS

50	2,133	LF	Furnish and install 12" PVC MAIN, DR 14, ALL DEPTHS, including fittings, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
----	-------	----	-------------------------------------------------------------------------------------------------------------------------------------------------	----------	----------

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
51	5	EA	Furnish and install NEW FIRE HYDRANT, ASSEMBLY - 6" VALVE AND DI LEAD PIPE, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
52	6	EA	Furnish and install TWO-INCH METER SETTING, long and short side, per detail shown on Plans, complete, per each for _____ Dollars and _____ Cents	\$ _____	\$ _____
53	1	EA	Furnish and install NEW 2" METER AT EXISTING CARWASH, transfer from existing main to be abandoned, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
54	1	EA	Furnish and install NEW 2" METER SETTING on existing 8" main, to serve Lot 1, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
55	13	EA	Furnish all labor, material, and equipment to RAISE VALVE CASTINGS, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
56	8	EA	Furnish and install 12" GATE VALVE WITH BOX, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
57	3	EA	Furnish all labor, material, and equipment to complete WET CONNECTIONS TO EXISTING MAINS, complete, per each for, Proposed 12 to Existing 12 _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
	1	EA	Proposed 8 to Existing 8 _____ _____ Dollars and _____ Cents	\$ _____	\$ _____
58	1	LS	Furnish all labor, material, and equipment to CUT AND PLUG EXISTING 8" BRANCH on existing 12" x 8" Tee, complete, per lump sum for, _____ _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
59	2,133	LF	Furnish and install TRENCH SAFETY SYSTEM, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

TOTAL AMOUNT OF PROPOSAL "D" (Sum of Items 50 through 59)					
_____ Dollars and _____ Cents					
				\$ _____	

PROPOSAL "E": WASTEWATER IMPROVEMENTS

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
60	13	LF	Furnish and install 12" WASTEWATER LINE PVC, SDR 26 (0-8' DEEP), at the grades shown on the Plans, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
61	84	LF	Furnish and install 12" WASTEWATER LINE PVC, SDR 26 (8-10' DEEP), at the grades shown on the Plans, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
62	33	LF	Furnish and install 8" WASTEWATER LINE PVC, SDR 26 (0'-8' DEEP), at the grades shown on the Plans, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
63	367	LF	Furnish and install 8" WASTEWATER LINE PVC, SDR 26 (8'-10' DEEP), at the grades shown on the Plans, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
64	4	EA	Furnish and install WASTEWATER MANHOLE, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
65	3	EA	Furnish all labor, material, and equipment to construct MANHOLE ON EXISTING LINE, complete, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
66	7	VF	Furnish and install MANHOLE EXTRA DEPTH, complete, per vertical foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
BASE BID "A"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
67	6	VF	Furnish all labor, material, and equipment to RAISE EXISTING MANHOLE TO FINISHED GRADE, complete, per vertical foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
68	5	EA	Furnish and install SINGLE WASTEWATER SERVICE, from service wye to two-way cleanout at property line, as per detail shown on Plans, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
69	1	EA	Furnish and install DOUBLE WASTEWATER SERVICE, from manhole to new service manhole at property line, as per detail shown on Plans, per each for, _____ Dollars and _____ Cents	\$ _____	\$ _____
70	1	LS	Furnish all labor, material, and equipment to CONNECT TO EXISTING MAIN, complete, per lump _____ Dollars and _____ Cents	\$ _____	\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
 BASE BID "A"

Item No.	Estimated Quantity	Unit	Description and Price (in words)	Unit Price	Total Price
71	497	LF	Furnish and install TRENCH SAFETY SYSTEM, complete, per linear foot for,		
			_____ Dollars		
			and _____ Cents	\$ _____	\$ _____

TOTAL AMOUNT OF PROPOSAL "E"
 (Sum of Items 60 through 71)

_____ Dollars		\$ _____
and _____ Cents		\$ _____

TOTAL AMOUNT OF BASE BID "A"
 (Sum of Items 1 through 71)

_____ Dollars		\$ _____
and _____ Cents		\$ _____

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
 SUPPLEMENTAL BID "B"

BID SCHEDULE:

PROPOSAL "A": EROSION / SEDIMENTATION CONTROL

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
1	341	LF	Furnish and install SILT FENCE, complete, per linear foot for, _____ Dollars and _____ Cents		\$ -
2	1	LS	Furnish and install CONCRETE WASHOUT STATION, per detail shown on Plans, complete, per lump sum for, _____ Dollars and _____ Cents		\$ -
3	3,107	SY	Furnish and install REVEGETATION OF STREET R.O.W. (hydroseed including watering), complete, per square yard for, _____ Dollars and _____ Cents		\$ -

TOTAL AMOUNT OF PROPOSAL "A" (Sum of Items 1 through 3)					
				_____ Dollars	
				and _____ Cents	\$ -

CITY OF BURNET
 ECONOMIC DEVELOPMENT CORPORATION
 HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
 SUPPLEMENTAL BID "B"

PROPOSAL "B": STREET AND DRAINAGE IMPROVEMENTS

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
4	1	LS	Furnish all labor and equipment to complete MOBILIZATION for the project start, for the lump sum of, _____ Dollars and _____ Cents	_____	\$ _____ -
5	1	LS	Furnish PERFORMANCE AND PAYMENT BONDS. 100 percent, per requirements in specifications for the lump sum of, _____ Dollars and _____ Cents	_____	\$ _____ -
6	1.81	AC	Furnish all labor, material, and equipment to CLEAR AND GRUB AND ROUGH CUT STREET INCLUDING DEMOLITION OF THE EXISTING STREET, complete, per acre for, _____ Dollars and _____ Cents	_____	\$ _____ -
7	6,267	SY	Furnish all labor, material, and equipment for SUBGRADE PREPARATION (3' BEHIND CURB) including 8" of moisture conditioned subgrade, _____ Dollars and _____ Cents	_____	\$ _____ -

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
SUPPLEMENTAL BID "B"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
8	6,267	SY	Furnish all labor, material, and equipment to install 11" CRUSHED STONE BASE (3' BEHIND CURB), per TxDOT Item 247, complete, per square yard for, _____ _____ Dollars and _____ Cents	_____	\$ _____ -
9	6,267	SY	Furnish all labor, material, and equipment to install GEOGRID, TENSAR TX5, per square yard for, _____ _____ Dollars and _____ Cents	_____	\$ _____ -
10	5,158	SY	Furnish all labor, material, and equipment to install 2" HMAC, Type D over 2" HMAC Type C, TxDOT Item 340, complete, per square yard for, _____ _____ Dollars and _____ Cents	_____	\$ _____ -
11	2,640	LF	Furnish all labor, material, and equipment to pour REINFORCED CONCRETE RIBBON CURB, complete, per linear foot for, _____ _____ Dollars and _____ Cents	_____	\$ _____ -
12	2,508	LF	Furnish all labor, material, and equipment to construct 5' CONCRETE SIDEWALK, including excavation and backfield, per detail shown on Plans, complete, per linear foot for, _____ _____ Dollars and _____ Cents	_____	\$ _____ -

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
SUPPLEMENTAL BID "B"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
13	3	EA	Furnish all labor, material, and equipment to install STREET SIGNS, complete, per each for, _____ Dollars and _____ Cents	_____	\$ _____ -
14	1	LS	Furnish all labor, material, and equipment to provide PAVEMENT STRIPING, including stop bars. _____ Dollars and _____ Cents	_____	\$ _____ -
15	1	LS	Furnish all labor, material, and equipment to provide GRADING FOR DRAINAGE PURPOSES, including all excavation and embankment, complete, per lot for, _____ Dollars and _____ Cents	_____	\$ _____ -
16	60	LF	Furnish all labor, material, and equipment to SAW CUT EXISTING ASPHALT AT HOUSTON CLINTON DRIVE, per linear foot for, _____ Dollars and _____ Cents	_____	\$ _____ -
17	4	LS	Furnish all labor, material, and equipment to REMOVE AND RELOCATE EXISTING ELECTRICAL TRANSFORMERS. _____ Dollars and _____ Cents	_____	\$ _____ -

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
SUPPLEMENTAL BID "B"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
18	1	LS	Furnish all labor, material, and equipment to REMOVE AND RELOCATE EXISTING GUARD RAILS. _____ Dollars and _____ Cents	_____	\$ _____ -
19A	55	LF	Furnish all and install 3 EA – 5' x 2' MULTIPLE BOX CULVERTS (ALL DEPTHS), per TxDOT Details, complete, per linear foot for, _____ Dollars and _____ Cents	\$ _____	\$ _____
20A	1	LS	Furnish and install PARALLEL HEADWALL WITH CONCRETE RIPRAP FOR OR 3 EA – 5' X 2' BOX CULVERTS at Station 0+22.53, per TxDOT Detail, upstream, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
21A	1	LS	Furnish and install PARALLEL HEADWALL WITH CONCRETE RIPRAP FOR OR 3 EA – 5' X 2' BOX CULVERTS at Station 0+77.42, per TxDOT Detail, upstream, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
22A	1	EA	Furnish and install CONNECTIONS TO EXISTING DRIVEWAYS WITH SAW CUT, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____
23A	1	LS	Furnish all labor, material, and equipment to CONSTRUCT, STAKE AND POUR CONCRETE TRICKLE CHANNEL, per standard detail, complete per lump sum for, _____ Dollars and _____ Cents	\$ _____	\$ _____

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
HOUSTON CLINTON DRIVE STREET IMPROVEMENTS
SUPPLEMENTAL BID "B"**

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Description and Price (in words)</u>	<u>Unit Price</u>	<u>Total Price</u>
24A	1	LS	Furnish all labor, material, and equipment to CONSTRUCT, STAKE AND POUR SPECIAL CURB INLET AND CONCRETE FLUME, per standard detail, complete per lump sum for,		
			_____ Dollars		
			and _____ Cents	\$ _____	\$ _____

**TOTAL AMOUNT OF PROPOSAL "B"
(Sum of Items 4 through 24)**

_____ Dollars		
and _____ Cents	\$	-

**TOTAL AMOUNT OF SUPPLEMENTAL BID "B"
(Sum of Items 1 through 24)**

_____ Dollars		
and _____ Cents	\$	-

**CITY OF BURNET
ECONOMIC DEVELOPMENT CORPORATION
281 SOUTH COMMERCIAL PARK SUBDIVISION IMPROVEMENTS
S. WATER STREET (U.S. HWY 281)**

It is understood that the description of work to be done at prices is intended principally to serve as a guide in evaluating bids and is not intended to fully describe all work required. It is further agreed that the work to be done and material to be furnished at unit prices may be increased or diminished as may be considered necessary in the opinion of the Engineer and approved by the Owner to complete the work fully as planned and contemplated, and that estimated quantities may be increased to cover additional work ordered by the Engineer and approved by the Owner, but not shown on the plans or required by the Specifications, in accordance with the provision of the General Conditions. Similarly, they may be decreased to cover deletion of the work so ordered.

The foregoing prices shall include all labor, materials, removal, overhead, profit, insurance, etc., to cover the finished work called for. Changes shall be proposed in accordance with applicable provisions of the General Conditions.

Bidder understands that the Owner reserves the right to reject any or all bids and to waive any informalities in the bidding.

The bidder agrees that his bid shall be good and may not be withdrawn for a period of ten (10) calendar days after the scheduled closing time for receiving bids.

Upon receipt of written notice of the acceptance of this bid, Bidder will execute the formal contract attached within ten (10) days and deliver Surety Bonds as required by the Special Conditions.

The bid security attached in the sum of five percent (5%) of the bid amount is to become the property of the Owner in the event the contract and bond are not executed within the time above set forth, as liquidated damages for the delay and additional expense to the Owner caused thereby.

Respectfully submitted: _____

Bidder: _____

Title: _____

(SEAL- if bid by
a corporation)

Address: _____

Phone No.: _____

Date: _____

PLAN HOLDERS LIST
281 SOUTH COMMERCIAL PARK
CITY OF BURNET
BID OPENING APRIL 7, 2021

	<u>COMPANY</u>	<u>EMAIL ADDRESS</u>	<u>EMAILED</u>	<u>PICKED UP</u>
1	JM Pipeline, LLC.	lydia@jmutilityllc.com	X	
2	Texas Bid Network	archie@napc.me	X	
3	Amtek USA	amtek.austin@amtekusa.com	X	
4	Cash Construction	cristina.martinka@ccctex.com	X	
5	Terra Path	Vanessa@terra-path.com	X	
6	Construct Connect	thessa.narido@constructconnect.com	X	
7	Joe Bland Construction	bhalko@joeblandconstruction.com	X	
8	Ross Construction, Inc.	randy@totalproject.net	X	
9	Austin Engineering	kvogt@aecoi.net	X	
10	Virtual Builders Exchange, LLC	brian@virtualbx.com	X	
11	Gage and Cade Construction	jason@gageandcadeconstruction.com	X	
12	Gloria Hoefle Balcones Ridge	ghbalconesridge@gmail.com	X	
13	Nelson Lewis Inc.	robin@nelsonlewisinc.com	X	
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				